

## Part 1, General (Deck Mix FP-PM)

### 1.01 Work Included

- A. Furnish all materials, labor, tools, and equipment to patch or overlay interior and/or exterior horizontal surfaces as designated by the owner.

### 1.02 Related Work

- A. Joint fillers
- B. Crack repair
- C. Pavement markings

### 1.03 Quality Assurance

- A. Provide a notarized certificate stating that the portland cement concrete meets the specified requirements and have the manufacturer's current printed literature on the specified product.
- B. Portland Cement concrete shall be tested by a certified testing laboratory, on a batch basis, to assure the product has been manufactured as specified on manufacturer's printed literature.
- C. Complete laboratory test reports, from an independently qualified testing laboratory, shall be made available for the specified product.

### 1.04 Delivery, Storage, and Handling

- A. Deliver the specified product in original, unopened containers with the manufacturer's name, labels, product identification, and batch numbers.
- B. Store and condition the specified product as recommended by the manufacturer.

### 1.05 Job Conditions

- A. Environmental Conditions: Do not apply material in rainfall or if the ambient temperature will fall below 40 degrees F. within 24 hours of application.
- B. Protection: Precautions should be taken to avoid damage to any surface near the work zone due to mixing and handling of the portland cement concrete.

## Part 2, Products

### 2.01 Acceptable Products

- A. Deck Mix FP-PM as supplied by U.S. Concrete Products, LLC, Timonium, Maryland.
- B. Substitutions: The use of other than the specified product will be considered providing the contractor requests its use in writing to the Engineer. This request shall be accompanied by a certificate of compliance from an approved independent testing laboratory that the proposed substitute product meets or exceeds the specified performance criteria, tested in accordance with the specified test standards.

### 2.02 Performance Criteria

- A. Properties of the mixed portland cement concrete:
  - 1. Working Time: 40 minutes
  - 2. Finishing Time: 50-60 minutes
  - 3. Color: concrete gray
  - 4. Flow: 100-200% (ASTM C109)
- B. Properties of the cured portland cement concrete:
  - 1. Compressive Strength (ASTM C-109 Modified)
    - a. 3 days 2000 psi
    - b. 7 days 3000 psi
    - c. 28 days 6000 psi
  - 2. Splitting Tensile Strength (ASTM C-496) at 28 days: 850 psi min.
  - 3. Flexural Strength (Modulus of Rupture)(ASTM C-78) at 28 days: 1000 psi min.
  - 4. Bond Strength (ASTM C-882 Modified) at 28 days: 1200 psi min.
  - 5. Length Change (ASTM C-157 - Dry Cured): -.02% @ 28 days - maximum

### 2.03 Materials

- A. Portland cement concrete:
  - 1. DECK MIX FP-PM shall be a blend of selected portland cements, specially graded aggregates and admixtures for controlling setting time, water reducers for workability and a corrosion inhibitor.
  - 2. The ratio of water to DECK MIX FP-PM shall be 1:10 by weight.
  - 3. The material shall not contain asbestos, chlorides, nitrates, added gypsum, added lime, or high aluminum cements.
  - 4. The material shall be non-combustible, either before or after cure.

5. The portland cement concrete shall be supplied in a factory proportioned unit.
6. The portland cement concrete must be able to be finished with a power trowel.
7. The portland cement concrete must be placeable from 1 in. in depth up to full depth.

### Part 3, Execution

#### 3.01 Surface Preparation

- A. The surface must be mechanically prepared. Areas to be patched or overlaid must be clean and sound. All loose and deteriorated concrete shall be removed by mechanical means approved by the Engineer. Chip concrete substrate and prepare the substrate surface in accordance with ICRI Guideline 03731. Sandblast reinforcing steel to remove all contaminants and rust. For substrate preparation where corroded reinforcing steel caused deteriorated concrete follow ICRI Guideline 03730.
- B. Cracks in the substrate in the area of the patching or overlay work must be treated as directed by the Engineer.
- C. Extend all existing control and expansion joints through any patch or overlay. Install new joints as directed by the Engineer. Fill all joints as directed by the Engineer.

#### 3.02 Application

- A. Mixing the portland cement concrete: Mix manually or mechanically. Manually mix in a wheelbarrow or mortar box. Mechanically mix in appropriate sized mortar mixer. Pour approximately 2.5 qts. water into the mixing container. Add DECK MIX FP-PM while continuing to mix. Mix to a uniform consistency for a maximum of three minutes. Add remaining water to mix if a more loose consistency is desired (**Do not exceed 2.7 quarts of water per bag**). If manual mixing takes more than three minutes, mix small quantities. Should smaller quantities be needed, be sure the components are dosed in the correct ratio and that the DECK MIX FP-PM is uniformly pre-mixed before batching.
- B. Placement Procedure: DECK MIX FP-PM can be placed manually, mechanically or pneumatically. At the time of application, the substrate should be saturated surface dry with no standing water. After filling, consolidate, then screed. Allow mortar to set to desired stiffness. Then finish with trowel, manual or power for smooth surface. Broom or burlap drag for rough surface. Areas where the depth of the repair area to sound concrete is less than 3/4 in. shall be repaired with portland cement mortar. In areas where the depth of the repair is greater than 1 in., the repair shall be made with portland cement concrete.

- C. Curing is not required under most conditions. However, if ambient condition might cause premature surface drying-high winds, high temperatures, direct sunlight, low humidity, etc., use a fine mist of water, wet burlap, or non-solvent, water based curing compound, which has been pre-approved by the Engineer.
- D. Adhere to all limitations and cautions for the portland cement concrete in the manufacturers current printed literature.

### 3.03 Cleaning

- A. The uncured portland cement concrete can be cleaned from tools with water. The cured portland cement concrete can only be removed mechanically.
- B. Leave finished work and work area in a neat, clean condition without evidence of spillovers onto adjacent areas.